



**NOTES:**

1. Specific site conditions may require an increase in these dimensions or reinforcement. It is the customer's responsibility to ensure the concrete encasement is designed for the application. *Engineering advice may be required.*
2. A minimum concrete strength of 25MPa is recommended. The concrete should be vibrated to eliminate air pockets.
3. The finished level of the pavers must be flush with the top of the pit.
4. The paver course adjacent to the pit edge must be fully bonded to the pit edge.
5. Refer to ACO's latest installation instructions for complete details.

The electrical/communication enclosures shall be ACO Cablemate plastic pit(s) *type(s) ...and part no(s)...* with Galvanised Steel cover (for 330kg nominal wheel load) with *clear opening(s) .....* and *part no(s)...*

All materials and components within the scope of this system shall be obtained from this manufacturer and the work shall be carried out as specified in accordance with the manufacturer installation recommendations.