



NOTES:

1. The reinforced concrete slab and concrete topping to engineer's details and specifications
2. Waterproof membrane to be specified by engineers.
3. The finished level of the concrete topping must be approx. 3mm above the top of the channel edge.
4. Refer to ACO's latest installation instructions for standard installation details.

The grated trench drainage system shall be ACO Membrane Drain installed with the SlabDrain **H100K / H100KS*** system as manufactured by ACO Polycrete Pty Ltd.

The constant depth system shall be complete with the manufacturer's standard grate type & part no., locked down with 'Quicklok'. The channels shall be sealed with a proprietry flexible sealant. The system shall be supplied with all associated auxiliary attachments including clamping devices.

All materials and components within the scope of this system shall be obtained from this manufacturer and the work shall be carried out as specified on the drawings.

The system shall be installed in accordance with the manufacturer's printed instructions.

*** Delete where appropriate.**

Systems denoted with 'KS' indicate that the channel's protective rail is made from stainless steel.